


FOUO: COMMERCIAL IN CONFIDENCE

# CTO Briefing: Multi Technology – Local Fibre Network (MT-LFN) INTERNAL USE

F0020-21-24 // Rev 7.0 I // 08-07-2015



# Network Context




## Local Fibre network (LFN)



# Multi-Technology Local Fibre Network



## Opportunity: High Cost of fibre in the local network

- Civil cost & time of current LFN – Pit & Duct augmentation, FDH siting & install, reinstatement
- Fibre connectivity required for MTM: FTTN ‘micronodes’, FTTB, Technology on Demand, FTTPdp



## Solution : Multi-Technology LFN (MT-LFN)

- New LFN architecture optimised for MTM & variety of fibre connectivity requirements in Local Network
- Zero civils LFN build:
  - Reduce cable size to minimise duct congestion & augmentation
  - Reduce size and quantity of closures to minimise pit congestion & augmentation
  - Remove FDH cabinet, replaced with small underground closure
- Designed for ‘build on demand’ fibre in LN
- Single fibres rather than ribbon fibre for cable size reduction & handling
- Technology agnostic optical connectivity in Local Network



Comparative Cable Size





# Objectives – MT-LFN

## Objectives:

- Reduced day-one capital cost of building fibre 'deep' into the LN
- Reduce the chance of pit & duct congestion & civil works (duct and pit augmentation) to the absolute minimum
- Support 1% - 100% flexible density
- Technology agnostic LFN
  - Support any P2P or P2MP technology requiring fibre in LN. E.g. CSDs, FTTB, FTTdp, HFC, FOD, CSAS (Mobile backhaul), ...
- Provide connectivity for the MTM demand points.
- Hand over pre-proven MT-LFN Architecture & business case to delivery teams (via NFDR)

## Progress:

- CTO has been working in conjunction with our passive and active vendors to investigate methods of providing a suitable Multi-Technology LFN.
- Multiple FTTP and small FTTdp architectures were overlaid on a DA in Gosford to assist in the understanding of the architectures in an NBN Co environment.




# MT-LFN development - Test DA

There were two main methods investigated for supplying MTM connectivity:

- Variants of the FDH cabinet, both above and below ground
- Cascaded split for GPON


Generally each approach reduced the cost of the network from the baseline, with the most flexible approach ( a smaller variant FDH) showing the least savings.

CTO have used a "best of breed" approach to combine the hardware proposed to provide a flexible MT-LFN, a strategy for technology upgrades, and is also expected to significantly reduce costs.




# MT-LFN Overview

- Support mixture of fibre connectivity types
  - Point to multipoint (e.g. GPON, xPON, FTTdp)
    - Centralised split
    - Cascaded split
  - Point to point (e.g. micronode/CSD backhaul, FTTB, business services, HFC optical nodes etc)
- Flexible capacity to allow changing LN fibre requirements over time
- Future connections leverage off the initial install to allow for:
  - Copper remediation avoidance
  - Fibre / bandwidth on demand
  - Infill Greenfields
  - Cost effective FTTP
- **No Fibre Distribution Hubs (FDH)**, eliminating the need for large pits and street cabinet siting
- **No Local Joints (LJL), No Access Joints (AJL)** – replaced by small form factor **Flexibility Joint Location (FJL)**
- **Single fibre connectorised cables** (connectorised at multi-port or FTTdp end only) used between FJL and SFM/dp to drastically reduce duct augmentation.
- **Small footprint multi-ports with integral splitters** used to provide connection capacity closer to demand points and minimise large fibre count cables traversing through DAs. Split ratio at 1:32 maintained.
- Allows for a consistent and flexible **upgrade path** for higher speed demand (FTTdp, FTTP).





# Architecture comparison



# MT-LFN Overview – Flexibility Joint


The demarcation between the DFN and the LFN is a new **Flexibility Joint Location (FJL)**.

## Flexibility Joint Location

- Optical connectivity between DFN and LFN fibres
- Breaking DFN ribbons into individual fibres
- Support direct **point-to-point** splicing
  - 12F to 12F or 12F to 12x1F connections
- Support **Point-to-multi-point** via passive optical splitters (xPON technologies)
  - Tray mounted 1:4 or 1:8 **first-stage** splitters for cascaded PON splitting
  - Tray mounted 1:32 splitters for cascaded

## Splittered Small Form Factor Multipoint

A second stage split is located in the Small Footprint Multi-ports (S-MPT) and these are connected via single fibre cables ( using the existing SDS cables with OptiTap / HFOC connector at the S-MPT ) to the splitter at the FJL.






# Hardware Changes

|                       | Architecture 3.0 LFN    | MT-LFN                            |
|-----------------------|-------------------------|-----------------------------------|
| DFN / LFN Demarcation | 576 / 432 FDH           | Flexibility Joint Location        |
| HSD Cables            | 72 Fibre Ribbon         | 12 Fibre Ribbon                   |
| LJL                   | Corning ORS             | —                                 |
| AJL                   | Corning ORS             | Breakout Joint (BCL)              |
| LSS Cables            | 144 and 72 Fibre Ribbon | Single Fibre Cables (SDS)         |
| MSS Cables            | 12 Fibre Ribbon         | —                                 |
| Premises Connection   | Multi-ports             | Multi-ports with splitter (S-MPT) |




# Architecture comparison – Pit & Duct

Current (Type 2) Architecture



MT LFN FTP Architecture

Red text indicates a high probability of Augmentation




Red text indicates pit that would need to be replaced to fit the new components





# Material size comparisons








# New components: Splitter Multiport CORNING



- No change to existing width & depth
  - Length increase to 120mm
  - MPT Input changed from integrated connector to connector on cable tail (like existing TE SFM)
  - Input tail length to be determined by sample testing
  - Differentiation of input by connector labelling & colour
  - Input 'Female' OptiTap
  - Outputs 'Female' OptiTap
  - Trial SFM unit price
    - 4P \$319 (Type 2 \$150)
    - 8P \$415 (Type 2 \$215)
- No change to body width & depth
  - Body extra 39mm in length
  - No change to output tail length
  - Input tail length to be determined by sample testing (100 or 400mm)
  - Input 'Female' OptiTap
  - Outputs 'Female' OptiTap
  - 4P \$266 (Type 2
  - 8P \$400 (Type 2 \$215)




# New components: FJL -



## Flexibility Joint Location (FJL)

- TE 'Tenio' Closure
- Compact size with a splice capacity of 144 single fibre splices
- 8 'off tray' splitter positions within closure accepting up to 1:64 splitters
- Supports direct point-to-point and PON connections
- Supports minimal first install with splitters and cables added when required for growth
- Modular base accepting multiple cable types
- Gel technology to seal cable entry




F0020-21-24 // Rev 7.0 // 08-07-2015

FOUO: COMMERCIAL IN CONFIDENCE




# New components: BCL – Breakout closure




## Breakout Closure Location (BCL)

- Breakout of stranded multi fibre cable to smaller fibre count sheaths
- Very compact size with a splice capacity of up to 12 single fibre splices
- Supports main stub or looped cable applications
- Can support splitters if required
- Gel technology to seal cable entry





# MT-LFN Evaluation Methodology



# Trial : Scope & purpose

- Scope
  - 100% FTTP FSAMs
  - Underground only (aerial architecture not ready yet)
  - FTTB supported
  - Construction trial only; does not require service activation
    - *But will need a plan to support service activation (IT, SOPS)*
  - Predicted capability delivery tasks & costs (E&DS, IT, Construction Operations)
- Purpose
  - Measure cost benefits of MT-LFN vs current LFN architecture



# Multi Technology-Local Fibre Network trial




## New LFN architecture

- Optimised for MTM
- Reduced cost and time to build

## Architecture trial

- Completed:
  - Redesign of Type 2 FTTP FSAMs to confirm cost savings predicted in design trial
- Underway:
  - Regional Deployment leading construction of redesigned FSAMs, to validate suitability of architecture and expected savings
  - Metrics will be collected and reviewed regularly throughout construction with CS&P




Design trial results





# Construction trial timeline



## **3BRA-10** Ballarat Vic SAM 10

- Construction: Decon
- RFP executed, kick-off meeting held, Remediation walkout complete


## **3KAL-07** Karingal Vic SAM 7

- Construction: Transfield
- RFP submitted. Remediation walkout 22 June 15




# Trial FSAM 1: 3BRA-10 (Ballarat, VIC)

| 3BRA-10 (NDD data)  |            |
|---|------------|
| Total GNAFs (a+b)   | 2294       |
| a. Aerial GNAF  | 0          |
| b. Underground GNAF   | 2294       |
| Telstra duct - total conduit used (km) (a+b)                    | 58.6       |
| a. Telstra duct - total used - occupied (km)                    | 53.4       |
| b. Telstra duct - total used - unoccupied (km)                  | 5.3        |
| Distribution Fibre - total (km) (a+b)                           | 31.5       |
| a. Distribution Fibre - outside FSAM Boundary (km)              | 19         |
| b. Distribution Fibre - inside FSAM Boundary (km) (i+ii)        | 12.5       |
| i. Distribution Fibre - inside FSAM Boundary - underground (km) | 12.5       |
| ii. Distribution Fibre - inside FSAM Boundary - aerial (km)     | 0          |
| Duct - Remediation (km)   | 0          |
| Duct - Augmentation (km)  | 1          |
| Duct - New Build (km)   | 9.1        |
| Telstra Pits - total used (a+b+c)                               | 1439       |
| a. Telstra Pits - utilised                                      | 1270       |
| b. Telstra Pits - remediation required                          | 100        |
| c. Telstra Pits - OH&S Impact (Field assessment required)       | 69         |
| NBNCo Pits - new build  | 95         |
| Cabinets - total (a+b)  | 15         |
| a. FDH Cabinets (external)                                      | 15         |
| b. PDH Cabinets (internal)                                      | 0          |
| POI   | 3BRA       |
| Approx. max straight line OLT-ONT distance                      | 11km       |
| MDUs  | 72 (12 >4) |
| Lead RD Designer  | Transfield |
| Construction Partner  | Corning    |
| Lead vendor   | Corning    |





# Trial FSAM 2: 3KAL-07 (Karingal, VIC)




| 3KAL-07 (NDD data)  |            |
|---|------------|
| Total GNAFs (a+b)   | 2160       |
| a. Aerial GNAF  | 502        |
| b. Underground GNAF                                       | 1658       |
| Duct - Augmentation (km)                                  | 2.5        |
| Duct - New Build (km)                                     | 7.2        |
| Telstra Pits - total used (a+b+c)                         | 1759       |
| a. Telstra Pits - utilised                                | 1583       |
| b. Telstra Pits - remediation required                    | 78         |
| c. Telstra Pits - OH&S Impact (Field assessment required) | 98         |
| NBNCo Pits - new build                                    | 32         |
| Cabinets - total (a+b)                                    | 14         |
| a. FDH Cabinets (external)                                | 14         |
| b. PDH Cabinets (internal)                                | 0          |
| POI   | 3KAL       |
| Approx. max straight line OLT-ONT distance                | 8km        |
| MDUs  | 26 (4 > 4) |
| Lead RD Designer  | Transfield |
| Construction Partner                                      | Corning    |
| Lead vendor   | Corning    |







# Trial sites density comparison




\*3BRA-10 FSAM



\*3BRA-10 comparison against 3BRU 07 FSAM and Brunswick FSA.



\*3KAL-07 FSAM



\*3KAL-07 comparison against 3BRU 07 FSAM and Brunswick FSA.

- Outside of HFC footprint – low density
- Cover significantly more area than same serviceable premises in metro
- Each FSAM (2000 SP) is same area as entire Brunswick FDA (20,000 SP)
- Requires longer cable runs
- More direct buried copper



# Next Steps

- Path to General deployment
  - Network Release
    - Construction Trial support - manual
    - Formalisation into Passive Network Architecture (Candidate NR10)
  - IT Support
    - PNI / spatial: Recording,
    - Fulfilment: network resource reservation, allocation logic
- Use cases
  - MT-LFN for Greenfields SDU
  - MT-LFN for Greenfields MDU
  - MT-LFN + FTTP
    - CSD alternative
- Other support required...
  - Construction
  - Build drop
  - Testing
  - Operational acceptance
  - Complex premises & MDUs?

